

GPS #: 3116

Date Destroyed:

Date Revised: 12/12/2010

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 769/G-7

City / Location: Orange

Scale Factor: 0.99998940

Ellipsoid Red. Factor: 0.99999626

Combination Factor: 0.99998567

Convergence Angle: -00 52 51.02938

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 48 56.65704	117 51 10.56954	2244191.762	6074796.049	78.107
2007.00	33 48 56.67344	117 51 10.58654	2244193.44	6074794.64	

References: PMB 238/18-19, RSB 149/10-20, CR 2002-1592, CR 2003-0201, CR 2010-0961, CR 2010-2259

Description:

FD ORIGINAL MONUMENT PER CR 2010-0961, IN LIEU OF PRVIOUSLY DESCRIBED PK NAIL WITH TAG STAMPED "LS 5411", FLUSH. MONUMENT WAS RESET PER CORNER RECORD #2003-201B. ORIGINAL MONUMENT BEING "T" SCRIBED IN CONC., DOWN 1.6' IN O.C.S. WELL MONUMENT. STATION IS LOCATED ALONG THE CENTERLINE OF TAFT AVE. 3.38' W'LY FROM ITS INTER WITH GLASSELL ST.

