

GPS #: **3118**

Date Destroyed:

Date Revised: 6/9/2008

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 799/G-2

City / Location: Orange

Scale Factor: 0.99998747

Ellipsoid Red. Factor: 0.99999594

Combination Factor: 0.99998341

Convergence Angle: -00 52 51.30418

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 48 08.59620	117 51 11.06959	2239334.803	6074679.169	84.947
2007.00	33 48 08.61259	117 51 11.08626	2239336.48	6074677.79	

References: MM 534/37-38, RSB 149/10-20, CR 2007-2971, CR 2008-0186

Description:

FD PUNCHED HEX BAR, DOWN 1.2' IN O.C.S. WELL MONUMENT PER CR 2008-0186. STATION IS LOCATED ALONG THE CENTERLINE OF GLASSSELL ST. 5.00' N'LY FROM ITS INTER WITH COLLINS AVE.

