

GPS #: **3120R1**

Date Destroyed:

Date Revised: 2/22/2001

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 799/H-4

City / Location: Orange

Scale Factor: 0.99998544

Ellipsoid Red. Factor: 0.99999606

Combination Factor: 0.99998149

Convergence Angle: -00 52 44.89203

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 47 16.31800	117 50 59.40092	2234035.834	6075582.665	
2007.00	33 47 16.33437	117 50 59.41739	2234037.51	6075581.30	

References: RSB 149/10-20, CR 2000-0301

Description:

FD GEAR SPIKE AND WASHER STAMPED "LS 5312" FLUSH IN LIEU OF PK NAIL AND TIN FLUSH IN A.C. SURFACE AT THE APPARENT CENTERLINE INTER OF CHAPMAN AVE. AND CENTER ST AFTER CONSTRUCTION 6/7/00.

