

GPS #: **3122R1**

Date Destroyed:

Date Revised: 2/6/2001

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 799/H-6

City / Location: Santa Ana

Scale Factor: 0.99998346

Ellipsoid Red. Factor: 0.99999597

Combination Factor: 0.99997943

Convergence Angle: -00 52 34.22620

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 46 23.84914	117 50 39.99146	2228707.646	6077139.561	
2007.00	33 46 23.86560	117 50 40.00778	2228709.33	6077138.21	

References: RSB 62/18, RSB 149/10-20, CR 2001-0353

Description:

FD PUNCHED SPIKE AND ALUMINUM WASHER STAMPED "SANTA ANA SURVEY" IN LIEU OF SQUARE SHAFT. MONUMENT HAS BEEN RESET PER CORNER RECORD # 2001-0353. STATION IS LOCATED AT CENTERLINE INTER OF CAMBRIDGE ST. AND FAIRHAVEN AVE.

