

GPS #: **3129R1**

Date Destroyed:

Date Revised: 8/16/2016

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 769/H-6

City / Location: Orange

Scale Factor: 0.99999049

Ellipsoid Red. Factor: 0.99999479

Combination Factor: 0.99998527

Convergence Angle: -00 52 33.72880

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 49 23.05466	117 50 39.08632	2246819.109	6077492.920	
2007.00	33 49 23.07108	117 50 39.10345	2246820.79	6077491.50	

References: ORANGE TIE BOOK PAGE 405, RSB 149/10-20, CR 2007-2762, CR 2008-0005

Description:

FD SPIKE AND WASHER WITH TAG STAMPED "LS 5411" FLUSH PER CR 2008-0005 IN LIEU OF PUNCHED SPIKE, FLUSH. STATION IS LOCATED AT CENTERLINE INTER OF MEATS AVE. AND CAMBRIDGE ST.

NO
LOCATION
MAP