

GPS #: 3147

Date Destroyed:

Date Revised: 8/8/2006

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 800/B-5

City / Location: Orange

Scale Factor: 0.99998443

Ellipsoid Red. Factor: 0.99999387

Combination Factor: 0.99997830

Convergence Angle: -00 51 42.64963

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 46 49.74743	117 49 06.13355	2231205.058	6085101.117	128.057
2007.00	33 46 49.76365	117 49 06.14970	2231206.72	6085099.78	

References: RSB 149/10-20, CR 2005-1257

Description:

FD PUNCHED 2 1/2" O.C.S. ALUMINUM CAP, STAMPED "10-73", DOWN 1.5' IN O.C.S. WELL MONUMENT. STATION IS LOCATED AT CENTERLINE INTER OF LA VETA AVE. AND PROSPECT AVE.

