

GPS #: **3169R1**

Date Destroyed:

Date Revised: 3/6/2013

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 800/D-3

City / Location: Unin., Orange County

Scale Factor: 0.99998695

Ellipsoid Red. Factor: 0.99998983

Combination Factor: 0.99997678

Convergence Angle: -00 51 08.93495

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 47 55.24760	117 48 04.78031	2237747.834	6090377.799	
2007.00	33 47 55.26358	117 48 04.79684	2237749.47	6090376.43	

References: A/4-9 1037, RSB 149/10-20, CR 2008-1445, CR 2012-0225, CR 2012-3440

Description:

FD PUNCHED 2-1/2" BRASS DISK STAMPED "LS 7052" PER CR 2012-3440 IN LIEU OF, PUNCHED 3" O.C.S. ALUMINUM CAP, STAMPED "FEB 74", DOWN 1.6' IN O.C.S. WELL MONUMENT. STATION IS LOCATED AT CENTERLINE INTER OF BOND AVE. AND RANCHO SANTIAGO BLVD.

