

GPS #: 3185

Date Destroyed:

Date Revised: 7/10/2001

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 800/F-3

City / Location: Orange

Scale Factor: 0.99998607

Ellipsoid Red. Factor: 0.99997877

Combination Factor: 0.99996484

Convergence Angle: -00 50 38.84082

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 47 32.76248	117 47 10.01569	2235406.779	6094965.461	443.638
2007.00	33 47 32.77860	117 47 10.03211	2235408.43	6094964.10	

References: MM 431/17-19, RSB 149/10-20

Description:

FD PUNCHED SPIKE AND DOUBLE WASHER, FLUSH. STATION IS LOCATED AT CENTERLINE B.C. OF CHAPMAN, 2121.45' AS MEASURED ALONG THE CENTERLINE E'LY FROM ITS INTER WITH CANYON VIEW RD.

