

**GPS #:** **3192**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 770/F-7

City / Location: Unin., Orange County

Scale Factor: 0.99998909

Ellipsoid Red. Factor: 0.99998375

Combination Factor: 0.99997284

Convergence Angle: -00 50 33.69072

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 48 48.88677	117 47 00.64366	2243089.237	6095869.521	339.625
2007.00	33 48 48.90281	117 47 00.66042	2243090.88	6095868.13	

References: TRACT NO. 13833, TMB 690/21-24 & RSB 149/10-20

**Description:**

FD PUNCHED 2 1/4" BRASS CAP, STAMPED "CITY OF ORANGE ENGINEERING", DOWN 1.8' IN O.C.S. WELL MONUMENT. STATION IS LOCATED AT THE INTERSECTION OF THE NEW CENTERLINE OF SANTIAGO RD. AND ORANGE PARK BLVD.

