

GPS #: 3206R1

Date Destroyed:

Date Revised: 2/27/2013

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 770/G-2

City / Location: Anaheim

Scale Factor: 0.99999543

Ellipsoid Red. Factor: 0.99999074

Combination Factor: 0.99998617

Convergence Angle: -00 50 25.07871

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 51 18.80159	117 46 44.97173	2258222.294	6097413.967	
2007.00	33 51 18.81787	117 46 44.98810	2258223.96	6097412.61	

References: MM 329/24-27, RSB 149/10-20, CR 2012-2821

Description:

FDGEAR SPIKE AND WASHER STAMPED "LS 5411"
FLUSH PER CR 2012-2821 IN LIEU OF PUNCHED
SPIKE AND WASHER, STAMPED "RCE 14010",
STATION IS LOCATED AT CENTERLINE INTER OF
ANAHEIM HILLS RD. AND CAMINO CORRER.

