

GPS #: **3215R1**

Date Destroyed:

Date Revised: 2/7/2001

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 770/G-4

City / Location: Anaheim

Scale Factor: 0.99999326

Ellipsoid Red. Factor: 0.99998260

Combination Factor: 0.99997586

Convergence Angle: -00 50 14.00546

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 50 29.00176	117 46 24.82086	2253163.929	6099039.679	
2007.00	33 50 29.01791	117 46 24.83761	2253165.58	6099038.29	

References: MM 543/31-35, RSB 149/10-20, CR 2001-0358

Description:

FD PUNCHED SPIKE AND BRASS OCS WASHER STAMPED "3215R1 01-01" FLUSH IN LIEU OF GEAR SPIKE AND WASHER, STAMPED "LS 5023". MONUMENT HAS BEEN RESET PER CORNER RECORD # 2001-0358. STATION IS LOCATED AT CENTERLINE INTER OF NOHL RANCH RD. AND STAGECOACH RD.

