

GPS #: **3224R2**

Date Destroyed:

Date Revised: 10/20/2008

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 800/F-2

City / Location: Unin., Orange County

Scale Factor: 0.99998740

Ellipsoid Red. Factor: 0.99998259

Combination Factor: 0.99996999

Convergence Angle: -00 50 31.52391

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 48 06.71863	117 46 56.70056	2238822.284	6096139.547	
2007.00	33 48 06.73471	117 46 56.71702	2238823.93	6096138.18	

References: A/4-9 1542, RSB 149/10-20, CR 2001-0360, CR 2007-1863, CR 2007-2934

Description:

FD PUNCHED SPIKE AND 1-1/2" OCS BRASS TAG "NO STAMPING" FLUSH, PER CR 2007-2934 IN LIEU OF: PUNCHED SPIKE AND OCS BRASS WASHER STAMPED "3224R1 01-01" FLUSH PER CR 2007-1863 IN LIEU OF PUNCHED SPIKE AND OCS WASHER. MONUMENT HAS BEEN RESET PER CORNER RECORD # 2001-0360. STATION IS LOCATED AT CENTERLINE INTER OF ORANGE PARK BLVD. AND AMAPOLA AVE.

