

GPS #: 3231R1

Date Destroyed:

Date Revised: 2/7/2001

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 800/H-4

City / Location: Orange

Scale Factor: 0.99998584

Ellipsoid Red. Factor: 0.99997909

Combination Factor: 0.99996493

Convergence Angle: -00 50 11.81194

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



| Epoch Adjustment | Latitude | Longitude | Northing (ft) | Easting (ft) | Ellipsoid Height (ft) |
|------------------|----------------|-----------------|---------------|--------------|-----------------------|
| 1991.35 | 33 47 26.69788 | 117 46 20.82914 | 2234732.932 | 6099107.274 | |
| 2007.00 | 33 47 26.71410 | 117 46 20.84546 | 2234734.59 | 6099105.92 | |

References: RSB 149/10-20, CR 2001-0361

Description:

FD 1 3/4" PUNCHED BRASS OCS DISK DOWN 2.0' IN OCS WELL MONUMENT IN LIEU OF SPIKE AND WASHER, STAMPED "LS 3236". MONUMENT HAS BEEN RESET PER CORNER RECORD # 2001-0361. STATION IS LOCATED AT APPARENT CENTERLINE INTER OF NEWPORT AVE. AND WHITE OAK RIDGE.

