

GPS #: 3250

Date Destroyed:

Date Revised: 4/11/2011

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 771/B-3

City / Location: Anaheim

Scale Factor: 0.99999351

Ellipsoid Red. Factor: 0.99995985

Combination Factor: 0.99995336

Convergence Angle: -00 49 11.43595

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 50 34.81428	117 44 30.95826	2253612.547	6108651.369	839.096
2007.00	33 50 34.83054	117 44 30.97476	2253614.21	6108650.00	

References: PMB 213/13-14, RSB 149/10-20, CR 2007-2691, CR 2011-0325

Description:

FD PUNCHED 2" BRASS CAP, DOWN 1.2' IN WELL MONUMENT PER CR 2007-2691, STATION IS LOCATED AT CENTERLINE INTER OF SERRANO AVE. AND CANYON RIM RD.

