

GPS #: 3254

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 770/H-4

City / Location: Anaheim

Scale Factor: 0.99999310

Ellipsoid Red. Factor: 0.99997472

Combination Factor: 0.99996782

Convergence Angle: -00 49 53.22792

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 50 25.25961	117 45 47.01037	2252739.251	6102223.160	528.378
2007.00	33 50 25.27602	117 45 47.02700	2252740.93	6102221.78	

References: MM 321/9-18, RSB 149/10-20

Description:

FD PUNCHED SPIKE AND WASHER (ILLEGIBLE) DOWN 0.1'. ACCEPTED AS SPIKE AND WASHER STAMPED "LS 2921" PER MM 321/9-18. STATION IS LOCATED AT CENTERLINE B.C. OF WALNUT CANYON RD., 346.99' NE'LY FROM ITS CENTERLINE INTER WITH NOHL RANCH RD.

