

GPS #: 3259R1

Date Destroyed:

Date Revised: 10/31/2006

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 770/H-2

City / Location: Anaheim

Scale Factor: 0.99999535

Ellipsoid Red. Factor: 0.99998346

Combination Factor: 0.99997881

Convergence Angle: -00 49 55.76311

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 51 17.13632	117 45 51.62382	2257988.315	6101910.211	R1
2007.00	33 51 17.15279	117 45 51.64013	2257990.00	6101908.86	

References: MM 412/32-35, RSB 149/10-20, RS 2006-1114

Description:

FD PUNCHED SPIKE AND WASHER STAMPED "RCE 11066" IN LIEU OF NAIL WITH BRASS WASHER, STAMPED "LS 3610", FLUSH. MONUMENT WAS RESET PER RS 2006-1114. STATION IS LOCATED AT CENTERLINE E.C. OF OLD BRIDGE RD., 1564.14' S'LY MEASURED ALONG THE CENTERLINE FROM ITS CENTERLINE INTER WITH MILL STREAM CIRCLE.

