

GPS #: **3277**

Date Destroyed:

Date Revised: 3/25/2014

Benchmark Designation:

OCS Index Map: 1L

Page/Grid: 768/J-2

City / Location: Anaheim

Scale Factor: 0.99999502

Ellipsoid Red. Factor: 0.99999775

Combination Factor: 0.99999277

Convergence Angle: -00 54 54.74176

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 51 09.61644	117 54 55.69859	2257927.925	6056017.872	47.129
2007.00	33 51 09.63287	117 54 55.71624	2257929.61	6056016.41	

References: RSB 149/21-36, CR 2014-0131

Description:

FD PUNCHED 2" BRASS CAP, DOWN 1.5' IN WELL MONUMENT. STATION IS LOCATED AT APPARENT CENTERLINE INTER OF COMMERCIAL ST. AND PATT ST.

