

**GPS #:** **3284**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 799/D-6

City / Location: Santa Ana

Scale Factor: 0.99998344

Ellipsoid Red. Factor: 0.99999974

Combination Factor: 0.99998317

Convergence Angle: -00 53 53.96073

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 46 23.23768	117 53 05.09059	2228835.513	6064891.400	5.495
2007.00	33 46 23.25396	117 53 05.10738	2228837.18	6064890.01	

References: MM 414/35-36, RSB 150/10-23

**Description:**

FD 3" BRASS CAP WITH CHISELED "+", DOWN 0.7' IN WELL MONUMENT STATION IS LOCATED ALONG THE CENTERLINE OF BRISTOL ST., 5.00' N'LY FROM ITS CENTERLINE INTER WITH MEMORY LN.

