

GPS #: **3501**

Date Destroyed:

Date Revised: 8/16/2004

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 798/B-5

City / Location: Garden Grove

Scale Factor: 0.99998452

Ellipsoid Red. Factor: 1.00000207

Combination Factor: 0.99998660

Convergence Angle: -00 56 53.19036

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 46 52.31329	117 58 31.24875	2232217.783	6037410.651	-43.327
2007.00	33 46 52.32944	117 58 31.26580	2232219.44	6037409.24	

References: GARDEN GROVE TIE BOOK 1 PAGE 68A, RSB 149/21-36, CR 2004-0233

Description:

FD DUREL BAR, DOWN 1.0' IN WELL MONUMENT.
STATION IS LOCATED AT CENTERLINE INTER OF
MAGNOLIA ST. AND LAMPSON AVE.

