

**GPS #:** 3511R1

Date Destroyed:

Date Revised: 5/21/2007

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 768/B-3

City / Location: Anaheim

Scale Factor: 0.99999487

Ellipsoid Red. Factor: 1.00000099

Combination Factor: 0.99999586

Convergence Angle: -00 56 54.83545

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 51 06.14955	117 58 34.24247	2257877.292	6037582.771	
2007.00	33 51 06.16571	117 58 34.26046	2257878.95	6037581.28	

References: PMB 45/50, RSB 149/21-36 CR 2003-1086

**Description:**

FD PUNCHED SPIKE AND OCS WASHER STAMPED "GPS 3511R1 4-03", FLUSH IN LIEU OF 2" BRASS CALIFORNIA DIVISION OF HWY.S CAP, IN CALIFORNIA DIVISION OF HWY.S WELL MONUMENT. MONUMENT WAS RESET PER CR2003-1086. STATION IS LOCATED ALONG THE CENTERLINE OF MAGNOLIA ST., 1775' +/- N'LY FROM ITS INTERSECTION WITH LA PALMA AVE.

