

GPS #: 3541

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 1L

Page/Grid: 739/B-4

City / Location: Fullerton

Scale Factor: 1.00000090

Ellipsoid Red. Factor: 0.99998606

Combination Factor: 0.99998696

Convergence Angle: -00 54 21.27598

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 53 19.23388	117 53 54.79830	2270947.167	6061360.640	291.364
2007.00	33 53 19.25040	117 53 54.81534	2270948.86	6061359.23	

References: RSB 149/21-36

Description:

FD SPIKE AND WASHER, ON SURFACE. STATION IS LOCATED AT APPARENT CENTERLINE B.C. OF ACACIA AVE., 2640' +/- N'LY FROM ITS INTER WITH DOROTHY LN.

