

GPS #: 3543

Date Destroyed:

Date Revised:

Benchmark Designation: 38-1 RE63 1954

OCS Index Map: 3L

Page/Grid: 708/B-4

City / Location: La Habra

Scale Factor: 1.00000997

Ellipsoid Red. Factor: 0.99998945

Combination Factor: 0.99999943

Convergence Angle: -00 56 55.35111

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 56 24.20172	117 58 35.18084	2290025.072	6038035.972	220.420
2007.00	33 56 24.21798	117 58 35.19828	2290026.74	6038034.53	

References: RSB 149/21-36

Description:

AKA BENCHMARK "LA-CO-38-1" - FD 2 1/2" BRASS L.A. COUNTY SURVEYOR DISK WITH DOME HEAD, STAMPED "BM 38-1 RE 63 1954", DOWN 1.0' IN WELL MONUMENT. STATION IS LOCATED NE OF THE INTER OF VALLEY HOME AVE. AND WHITTIER BLVD. AT THE CURB LINE AND NW EDGE OF WHEEL CHAIR RAMP.

