

GPS #: **3546R1**

Date Destroyed:

Date Revised: 4/3/2001

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 708/F-4

City / Location: La Habra

Scale Factor: 1.00001079

Ellipsoid Red. Factor: 0.99998378

Combination Factor: 0.99999457

Convergence Angle: -00 55 46.92530

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 56 40.13464	117 56 30.66105	2291463.524	6048552.001	
2007.00	33 56 40.15077	117 56 30.67836	2291465.18	6048550.57	

References: RSB 149/21-36, CR 2001-0678

Description:

FD PUNCHED SPIKE AND 1 1/2" OCS BRASS WASHER STAMPED "3546R1 02-01" FLUSH, IN LIEU OF PUNCHED BOAT SPIKE AND WASHER, STAMPED "LS 4016". MONUMENT WAS RESET PER CORNER RECORD # 2001-678. STATION IS LOCATED AT THE VISUAL CENTERLINE OF CYPRESS ST., 30'+/- N'LY FROM THE INTER OF BONNIE LN., 250'+/- S'LY OF THE COUNTY LINE.

