

GPS #: 3549R1

Date Destroyed: 7/26/2000

Date Revised:

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 708/J-3

City / Location: Brea

Scale Factor: 1.00001109

Ellipsoid Red. Factor: 0.99997956

Combination Factor: 0.99999065

Convergence Angle: -00 54 55.04290

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 56 45.87761	117 54 56.24662	2291915.934	6056514.645	
2007.00	33 56 45.89385	117 54 56.26396	2291917.60	6056513.21	

References: CR 2000-0039

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD PUNCHED SPIKE AND 1 1/2" OCS BRASS WASHER STAMPED "GPS 3549R" FLUSH IN A.C. IN LIEU OF ORIGINAL MONUMENT BEING A BOLT AND WASHER, ON SURFACE. STATION IS LOCATED AT APPARENT CENTERLINE OF PUENTE ST., 150'+/- N'LY FROM ITS INTER WITH WOODCREST AVE. MONUMENT WAS RESET PER CORNER RECORD # 2000-39