

GPS #: 3555

Date Destroyed: 7/25/2000

Date Revised:

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 738/A-3

City / Location: Unin., Orange County

Scale Factor: 1.00000330

Ellipsoid Red. Factor: 0.99999607

Combination Factor: 0.99999937

Convergence Angle: -00 57 08.07573

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 54 09.85043	117 58 58.33684	2276478.052	6035859.546	82.224
2007.00	33 54 09.86658	117 58 58.35442	2276479.71	6035858.09	

References: RSB 149/21-36

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD 3" I.P. AND PUNCHED SPIKE, DOWN 1.2' IN L.A.C.S. WELL MONUMENT. STATION IS LOCATED NE'LY 2000'+/- FROM THE INTER OF ROSECRANS AVE. AND BEACH BLVD. AT THE APPARENT CENTERLINE OF BEACH BLVD.