

GPS #: 3559

Date Destroyed:

Date Revised: 9/19/2007

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 709/B-5

City / Location: Brea

Scale Factor: 1.00000930

Ellipsoid Red. Factor: 0.99998670

Combination Factor: 0.99999600

Convergence Angle: -00 54 10.06351

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 56 11.04926	117 53 34.39408	2288286.227	6063354.238	277.965
2007.00	33 56 11.06579	117 53 34.41125	2288287.92	6063352.82	

References: MM 374/25-26, RSB 149/21-36, CR 2007-0045

Description:

FD PUNCHED 1 3/4" BRASS DISK IN CONC., STAMPED "RCE 23953", DOWN 0.85' IN TRIANGULAR WELL MONUMENT MARKED WATER. STATION IS LOCATED AT CENTERLINE INTERSECTION OF BREA BLVD. AND CANYON COUNTRY RD.

