

GPS #: **3561**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 739/C-2

City / Location: Fullerton

Scale Factor: 1.00000398

Ellipsoid Red. Factor: 0.99998968

Combination Factor: 0.99999366

Convergence Angle: -00 54 03.77272

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 54 23.84336	117 53 22.94625	2277435.189	6064148.265	215.613
2007.00	33 54 23.85997	117 53 22.96337	2277436.89	6064146.85	

References: FULLERTON TIE BOOK 19 PAGE 24-3, RSB 149/21-36, CR 2011-2798

Description:

FD GEAR SPIKE AND CITY OF FULLERTON WASHER FLUSH, STATION IS LOCATED AT CENTERLINE INTER OF LARK ELLEN DR. AND STATE COLLEGE BLVD.

