

GPS #: 3568R1

Date Destroyed:

Date Revised: 4/2/2001

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 739/C-2

City / Location: Fullerton

Scale Factor: 1.00000344

Ellipsoid Red. Factor: 0.99999021

Combination Factor: 0.99999364

Convergence Angle: -00 53 51.10718

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 54 12.65308	117 52 59.89780	2276273.643	6066072.983	
2007.00	33 54 12.66974	117 52 59.91486	2276275.35	6066071.57	

References: FULLERTON TIE BOOK 1 PAGE 19-13, RSB 149/21-36, CR 2001-675

Description:

FD PUNCHED SPIKE AND WASHER STAMPED "BADSON & ASSOC. LS 6154" FLUSH, IN LIEU OF PUNCHED SPIKE AND WASHER, STAMPED "LS 2988". MONUMENT WAS RESET PER CORNER RECORD # 2001-675. STATION IS LOCATED AT CENTERLINE INTER OF ASSOCIATED RD. AND ROLLING HILLS DR.

