

GPS #: **3587R1**

Date Destroyed:

Date Revised: 4/2/2001

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 767/D-1

City / Location: Cerritos

Scale Factor: 0.99999736

Ellipsoid Red. Factor: 1.00000313

Combination Factor: 1.00000049

Convergence Angle: -00 58 55.34836

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 52 02.15513	118 02 13.54919	2263849.422	6019186.144	
2007.00	33 52 02.17098	118 02 13.56701	2263851.05	6019184.67	

References: RSB 149/21-36, CR 2001-0673

Description:

FD PUNCHED SPIKE AND 1 1/2" OCS BRASS WASHER STAMPED "3587R1 02-01" FLUSH, IN LIEU OF SPIKE AND WASHER STAMPED "RCE 12979". MONUMENT WAS RESET PER CORNER RECORD # 2001-673. STATION IS LOCATED AT THE VISUAL CENTERLINE INTER OF CARNABY ST. AND KENSINGTON AVE.

