

GPS #: **3592**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 767/G-2

City / Location: Buena Park

Scale Factor: 0.99999601

Ellipsoid Red. Factor: 1.00000233

Combination Factor: 0.99999834

Convergence Angle: -00 58 04.13924

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 51 32.03622	118 00 40.35994	2260671.558	6026991.735	-48.756
2007.00	33 51 32.05200	118 00 40.37813	2260673.18	6026990.23	

References: RSB 149/21-36, CR 2008-2577

Description:

FD PUNCHED 2" O.C.S. CAP, STAMPED "RESET 3-83", DOWN 1.3' IN O.C.S. WELL MONUMENT. STATION IS LOCATED AT APPARENT CENTERLINE INTER OF ORANGETHORPE AVE. AND KNOTT AVE.

