

**GPS #:** **3617**

**Date Destroyed:** **7/26/2000**

**Date Revised:**

**Benchmark Designation:**

**OCS Index Map:** **3L**

**Page/Grid:** **797/F-3**

**City / Location:** **Cypress**

**Scale Factor:** **0.99998673**

**Ellipsoid Red. Factor:** **1.00000357**

**Combination Factor:** **0.99999030**

**Convergence Angle:** **-00 58 21.10854**

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 47 49.66975	118 01 11.24032	2238241.068	6024006.364	-74.629
2007.00	33 47 49.68574	118 01 11.25753	2238242.71	6024004.94	

**References:** **MM 330/48-50, RSB 149/21-36**

**Description:**

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD PUNCHED BOLT WITH WASHER (ILLEGIBLE) AND TIN, FLUSH. ACCEPTED AS PUNCHED BOLT AND TAG STAMPED "RCE 14010" PER MM 330/48-50. STATION IS LOCATED AT CENTERLINE INTER OF HOLDER ST. AND GRAND MANAN DR.