

GPS #: 3625R1

Date Destroyed:

Date Revised: 5/12/1999

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 797/J-4

City / Location: Garden Grove

Scale Factor: 0.99998551

Ellipsoid Red. Factor: 1.00000249

Combination Factor: 0.99998800

Convergence Angle: -00 57 27.98037

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 47 18.13798	117 59 34.55887	2234916.737	6032111.138	
2007.00	33 47 18.15419	117 59 34.57598	2234918.40	6032109.72	

References: CALTRANS AORO39C 0012, RSB 149/21-36, CR 0722

Description:

FD CALTRANS TYPE D SURVEY MONUMENT WITH 3" BRASS DISK STAMPED "STATE OF CALIFORNIA, DEPARTMENT OF TRANSPORTATION, RCE 26087" IN PLACE OF ORIGINAL "C" NAIL. STATION IS LOCATED AT CENTERLINE INTER OF BEACH BLVD. AND CHAPMAN AVE.

