

GPS #: 3634

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 797/F-6

City / Location: Garden Grove

Scale Factor: 0.99998444

Ellipsoid Red. Factor: 1.00000378

Combination Factor: 0.99998822

Convergence Angle: -00 58 21.21328

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 46 50.00828	118 01 11.43093	2232211.431	6023887.916	-78.940
2007.00	33 46 50.02457	118 01 11.44805	2232213.10	6023886.50	

References: RSB 149/21-36

Description:

FD PK NAIL AND 2 CITY OF GARDEN GROVE WASHERS FLUSH ON SURFACE. STATION IS LOCATED AT APPARENT CENTERLINE INTER OF KILLARNEY AVE. AND FRONTAGE RD. (SPRINGDALE), 60'+/- EAST FROM APPARENT CENTERLINE OF SPRINGDALE ST., 220'+/- S'LY FROM APPARENT CENTERLINE OF LAMPSON AVE.

