

**GPS #:** 3646R1

Date Destroyed:

Date Revised: 9/20/2009

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 738/D-1

City / Location: La Habra

Scale Factor: 1.00000586

Ellipsoid Red. Factor: 0.99999360

Combination Factor: 0.99999946

Convergence Angle: -00 56 06.83763

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 55 02.38157	117 57 06.89708	2281632.861	6045338.237	
2007.00	33 55 02.39784	117 57 06.91444	2281634.53	6045336.80	

References: RSB 149/21-36, CR 2003-1058, CR 2009-0685

## Description:

FD 2 1/2" BRASS DISK STAMPED "CALIF. DEPT. OF TRANSPORTATION", DOWN 0.6' IN WELL MON. MONUMENT WAS RESET PER CORNER RECORD #2003-1058 IN LIEU OF PUNCHED SPIKE AND O.C.S. WASHER FLUSH ON SURFACE. STATION IS LOCATED AT APPARENT CENTERLINE INTER OF IMPERIAL HWY. AND WALNUT ST.

