

GPS #: 3647R1

Date Destroyed:

Date Revised: 9/29/2009

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 708/D-7

City / Location: La Habra

Scale Factor: 1.00000716

Ellipsoid Red. Factor: 0.99999313

Combination Factor: 1.00000029

Convergence Angle: -00 56 21.19607

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 55 28.48689	117 57 33.02624	2284307.452	6043179.721	
2007.00	33 55 28.50315	117 57 33.04356	2284309.12	6043178.29	

References: RSB 149/21-36, CR 3647, CR 2008-2636

Description:

FD MAG NAIL AND WASHER STAMPED "LS 6970",
FLUSH IN LIEU OF PUNCHED SPIKE AND O.C.S.
WASHER FLUSH ON SURFACE. STATION IS
LOCATED AT APPARENT CENTERLINE INTER OF
LAMBERT RD. AND IDAHO ST.

