

**GPS #:** 3655

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 738/C-5

City / Location: Fullerton

Scale Factor: 1.00000082

Ellipsoid Red. Factor: 0.99999536

Combination Factor: 0.99999618

Convergence Angle: -00 56 34.86079

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 53 17.54975	117 57 57.89302	2271107.600	6040866.665	97.031
2007.00	33 53 17.56593	117 57 57.91047	2271109.26	6040865.22	

References: FULLERTON TIE BOOK 7 PAGE 1-28, RSB 149/21-36

## Description:

FD PUNCHED RAILRD. SPIKE AND WASHER, STAMPED "LS ----" (COVERED BY SPIKE), DOWN 0.15'. STATION IS LOCATED ALONG THE CENTERLINE OF GILBERT ST., 8.22' N'LY FROM ITS INTER WITH PIONEER AVE.

