

GPS #: **3663R1**

Date Destroyed:

Date Revised: 5/22/2003

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 738/F-5

City / Location: Fullerton

Scale Factor: 0.99999965

Ellipsoid Red. Factor: 0.99999581

Combination Factor: 0.99999545

Convergence Angle: -00 55 47.24483

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 52 52.32247	117 56 31.24253	2268438.416	6048129.324	
2007.00	33 52 52.33868	117 56 31.25985	2268440.08	6048127.89	

References: RSB 149/21-36, CR 2003-1087

Description:

SET PUNCHED SPIKE AND OCS WASHER STAMPED "GPS 3663R1 4-03", FLUSH, IN LIEU OF LARGE PK NAIL AND TIN AT THE APPARENT CENTERLINE INTER OF EUCLID ST. AND VALLEY VIEW DR. MONUMENT WAS RESET PER CR 2003-1087.

