

GPS #: **3668R1**

Date Destroyed:

Date Revised: 4/2/2001

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 738/E-2

City / Location: La Habra

Scale Factor: 1.00000438

Ellipsoid Red. Factor: 0.99998606

Combination Factor: 0.99999044

Convergence Angle: -00 55 59.21625

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 54 32.17703	117 56 53.02785	2278560.912	6046457.202	
2007.00	33 54 32.19329	117 56 53.04529	2278562.58	6046455.76	

References: MM 171/11-13, RSB 149/21-36, CR 2001-0665

Description:

FD PUNCHED SPIKE AND 1 1/2" OCS BRASS WASHER STAMPED "3668R1 02-01" FLUSH, IN LIEU OF PUNCHED SPIKE AND WASHER. MONUMENT WAS RESET PER CORNER RECORD # 2001-665. MONUMENT IS LOCATED AT THE CENTERLINE INTER OF EUCLID ST. AND COUNTRY HILLS DR.

