

GPS #: **3671R1**

Date Destroyed:

Date Revised: 4/2/2001

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 738/G-3

City / Location: Fullerton

Scale Factor: 1.00000258

Ellipsoid Red. Factor: 0.99999325

Combination Factor: 0.99999582

Convergence Angle: -00 55 29.82226

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 53 54.66580	117 55 59.53733	2274696.409	6050903.810	
2007.00	33 53 54.68202	117 55 59.55472	2274698.07	6050902.37	

References: FULLERTON TIE BOOK 4 PAGE 9-20, RSB 149/21-36, CR 2001-0664

Description:

FD PUNCHED SPIKE AND 1 1/2" OCS BRASS WASHER STAMPED "3671R1 02/01" FLUSH IN LIEU OF CONC. NAIL. MONUMENT WAS RESET PER CORNER RECORD # 2001-664. MONUMENT IS LOCATED AT THE CENTERLINE INTER OF DOMINGO RD. AND CATALINA RD.

