

**GPS #:** **3704**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 767/H-5

City / Location: Anaheim

Scale Factor: 0.99999182

Ellipsoid Red. Factor: 1.00000191

Combination Factor: 0.99999373

Convergence Angle: -00 57 46.35912

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



| Epoch Adjustment | Latitude       | Longitude       | Northing (ft) | Easting (ft) | Ellipsoid Height (ft) |
|------------------|----------------|-----------------|---------------|--------------|-----------------------|
| 1991.35          | 33 49 55.13374 | 118 00 08.00411 | 2250831.571   | 6029555.401  | -39.879               |
| 2007.00          | 33 49 55.14981 | 118 00 08.02175 | 2250833.22    | 6029553.94   |                       |

References: PMB 44/16, RSB 149/21-36, CR 2011-2495

**Description:**

**FD 2" PUNCHED BRASS CALIFORNIA DIVISION OF HWY.S DISK DOWN 1.0' IN WELL MONUMENT AT THE CENTERLINE INTER OF LINCOLN AVE. AND WESTERN AVE.**

