

GPS #: 3707R1

Date Destroyed:

Date Revised: 2/2/2010

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 768/A-6

City / Location: Anaheim

Scale Factor: 0.99999075

Ellipsoid Red. Factor: 1.00000143

Combination Factor: 0.99999218

Convergence Angle: -00 57 11.61526

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 49 29.41593	117 59 04.77801	2248143.076	6034845.092	
2007.00	33 49 29.43216	117 59 04.79553	2248144.74	6034843.64	

References: MM 107/24-26, RSB 149/21-36, CR 2001-0660, CR 2009-3261

Description:

FD GEAR SPIKE AND "CITY OF ANAHEIM SURVEY DIVISION" WASHER FLUSH IN LIEU OF 1" I.P. WITH BRASS NAIL IN WOOD PLUG. MONUMENT WAS RESET PER CORNER RECORD # 2001-660. MONUMENT IS LOCATED AT THE CENTERLINE INTER OF ORANGE AVE. AND DALE AVE.

