

**GPS #:** 3710

Date Destroyed:

Date Revised: 8/8/2006

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 767/G-6

City / Location: Anaheim

Scale Factor: 0.99999071

Ellipsoid Red. Factor: 1.00000246

Combination Factor: 0.99999317

Convergence Angle: -00 58 03.45784

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



| Epoch Adjustment | Latitude       | Longitude       | Northing (ft) | Easting (ft) | Ellipsoid Height (ft) |
|------------------|----------------|-----------------|---------------|--------------|-----------------------|
| 1991.35          | 33 49 28.51484 | 118 00 39.11997 | 2248185.412   | 6026885.433  | -51.361               |
| 2007.00          | 33 49 28.53079 | 118 00 39.13751 | 2248187.05    | 6026883.98   |                       |

References: RSB 149/21-36, CR 2006-0338

**Description:**

FD PUNCHED SPIKE AND O.C.S. WASHER FLUSH AT THE APPARENT CENTERLINE INTER OF ORANGE AVE. AND KNOTT AVE.

