

GPS #: 3717R1

Date Destroyed: 7/25/2000

Date Revised: 5/22/2003

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 767/A-7

City / Location: Cypress

Scale Factor: 0.99999064

Ellipsoid Red. Factor: 1.00000411

Combination Factor: 0.99999474

Convergence Angle: -00 59 47.14626

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 49 26.67193	118 03 47.80990	2248271.983	6010965.504	
2007.00	33 49 26.68796	118 03 47.82734	2248273.63	6010964.06	

References: MM 232/1-3, RSB 149/21-36 CR 2003-1092, CR 2006-0615

Description:

FD SPIKE AND OCS WASHER STAMPED "GPS 3717R1 4-03", FLUSH, IN LIEU OF FD 3/4" I.P. WITH NOTHING IN IT. MONUMENT WAS RESET PER CR 2003-1092. LOCATED AT THE CENTERLINE INTER OF BLOOMFIELD ST. AND ORANGE AVE.

NO
LOCATION
MAP