

GPS #: **3721R1**

Date Destroyed:

Date Revised: 5/22/2003

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 797/D-1

City / Location: Cypress

Scale Factor: 0.99998959

Ellipsoid Red. Factor: 1.00000372

Combination Factor: 0.99999331

Convergence Angle: -00 58 54.77931

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 49 01.18311	118 02 12.51364	2245557.051	6018959.970	
2007.00	33 49 01.19919	118 02 12.53129	2245558.70	6018958.51	

References: RSB 149/21-36, CR 2003-1090

Description:

SET 2" IP WITH BRASS NAIL AND 1-1/4" OCS TAG STAMPED "GPS 3721R1 4-03", DOWN 0.7' IN WELL, IN LIEU OF PUNCHED CUT SPIKE FLUSH WITH FOUR O.C.S. TANGENT OVER TIES AT THE APPARENT CENTERLINE INTER OF BALL RD. AND WALKER ST. MONUMENT WAS RESET PER CR2003-1090.

