

GPS #: 3730

Date Destroyed:

Date Revised: 5/14/2009

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 797/H-1

City / Location: Stanton

Scale Factor: 0.99998858

Ellipsoid Red. Factor: 1.00000267

Combination Factor: 0.99999125

Convergence Angle: -00 57 45.91872

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 48 36.27615	118 00 07.20265	2242860.291	6029489.063	-55.797
2007.00	33 48 36.29222	118 00 07.22009	2242861.94	6029487.62	

References: PMB 243/14-15, RSB 149/21-36, CR 2008-0481, CR 2008-1153, CR 2009-1662

Description:

FD PUNCHED HEX BAR DOWN 0.8' IN O.C.S. WELL
PER CR 2008-0481. MONUMENT IS LOCATED ALONG
THE CENTERLINE OF CERRITOS AVE., 5.0' W'LY
FROM ITS CENTERLINE INTER WITH WESTERN AVE.

