

GPS #: **3733**

Date Destroyed:

Date Revised: 9/9/2010

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 797/E-2

City / Location: Cypress

Scale Factor: 0.99998854

Ellipsoid Red. Factor: 1.00000362

Combination Factor: 0.99999216

Convergence Angle: -00 58 37.62919

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 48 35.40070	118 01 41.30426	2242906.223	6021548.387	-75.649
2007.00	33 48 35.41686	118 01 41.32161	2242907.88	6021546.95	

References: PMB 242/44-47, RSB 149/21-36, CR 2010-1464, CR 2010-2443

Description:

FD 2 1/2" PUNCHED BRASS O.C.S. DISK DOWN 1.5' IN O.C.S. WELL MONUMENT AT THE CENTERLINE INTER OF CERRITOS AVE. AND VALLEY VIEW ST.

