

GPS #: **3741R1**

Date Destroyed:

Date Revised: 8/16/2004

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 797/A-3

City / Location: Los Alamitos

Scale Factor: 0.99998757

Ellipsoid Red. Factor: 1.00000430

Combination Factor: 0.99999187

Convergence Angle: -00 59 46.95197

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 48 11.07482	118 03 47.45633	2240630.952	6010862.447	
2007.00	33 48 11.09086	118 03 47.47356	2240632.60	6010861.02	

References: PMB 228/44-46, RSB 149/21-36, CR 96-376

Description:

FD BRASS CAP STAMPED "CITY OF LOS ALAMITOS", DOWN IN TYPE "A" WELL MONUMENT IN LIEU OF FD PUNCHED SPIKE AND WASHER STAMPED "LS 2304" FLUSH PER CORNER RECORD 96-376, ALONG THE CENTERLINE OF KATELLA AVE., E'LY 0.17' FROM ITS CENTERLINE INTER WITH BLOOMFIELD AVE.

