

GPS #: 3750R1

Date Destroyed:

Date Revised: 2/25/2013

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 798/A-2

City / Location: Garden Grove

Scale Factor: 0.99998756

Ellipsoid Red. Factor: 1.00000213

Combination Factor: 0.99998969

Convergence Angle: -00 57 11.21742

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 48 10.74120	117 59 04.05398	2240190.392	6034773.875	
2007.00	33 48 10.75747	117 59 04.07122	2240192.06	6034772.45	

References: RSB 116/41, RSB 149/21-36, CR 2010-2600, CR 2012-1972

Description:

FD 2-1/2" OCS ALUM. CAP FLUSH IN AC PER CR 2012-1972, IN LIEU OF PUNCHED DUREL BAR DOWN 1.3' IN O.C.S. WELL MONUMENT WITH FOUR PUNCHED CUT SPIKE AND WASHERS TIES AT THE CENTERLINE INTER OF KATELLA AVE. AND DALE ST.

