

GPS #: 3755R1

Date Destroyed: 1/26/2004
Date Revised: 4/2/2001
Benchmark Designation:
OCS Index Map: 3L
Page/Grid: 796/J-6
City / Location: Seal Beach

Scale Factor: 0.99998441
Ellipsoid Red. Factor: 1.00000481
Combination Factor: 0.99998922
Convergence Angle: -01 00 04.36948

Factors and Convergence Angle based on
the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 46 49.24016	118 04 19.15231	2232406.710	6008043.581	
2007.00	33 46 49.25643	118 04 19.16950	2232408.38	6008042.16	

References: A/4-11&12 496, RSB 149/21-36, CR 2001-0658

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD GEAR SPIKE AND WASHER STAMPED "LS 7076" FLUSH IN LIEU OF CONC. NAIL AND TIN. MONUMENT WAS RESET PER CORNER RECORD # 2001-658. MONUMENT IS LOCATED AT THE CENTERLINE INTER OF SEAL BEACH BLVD. AND ST. CLOUD DR.

NO
LOCATION
MAP