

GPS #: **3855R1**

Date Destroyed: **9/16/2009**

Date Revised: **9/16/2009**

Benchmark Designation:

OCS Index Map: **3L**

Page/Grid: **709/A-7**

City / Location: **Brea**

Scale Factor: **1.00000587**

Ellipsoid Red. Factor: **0.99998988**

Combination Factor: **0.99999574**

Convergence Angle: **-00 54 37.81884**

*Factors and Convergence Angle based on
the 1991.35 Epoch Adjustment positions.*

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 55 02.52649	117 54 24.90265	2281427.622	6058988.968	
2007.00	33 55 02.54287	117 54 24.91989	2281429.30	6058987.54	

References: PMB 195/35-37, RSB 149/21-36, CR 2001-0657

Description:

REPORTED DESTROYED (PER CORNER RECORD 2009-0037) - ORIGINAL DESCRIPTION BEING:FD PUNCHED SPIKE AND OCS WASHER STAMPED "3855R1 02-01" FLUSH IN POUR ROCK IN LIEU OF SPIKE AND CALIFORNIA DIVISION OF HWY.S WASHER. MONUMENT WAS RESET PER CORNER RECORD # 2001-657. MONUMENT IS LOCATED AT THE CENTERLINE INTER OF IMPERIAL HWY. AND BERRY ST.